



## Use of the Definition of Waste Code of Practice

### Major Projects

Steve Phipps

Senior Materials Engineer



**Balfour Beatty**

## Applications Used

### ❖ **Re-use on site of origin**

Naturally occurring earthworks materials

Aggregates recycling

### ❖ **Re-use of contaminated materials on site of origin**

Landfill Arisings

Tar Bound Materials

### ❖ **Direct Transfer between sites**

Both imported and exported

## **Re-use on Site of Origin – M25 DBFO**

❖ **M25 30 year concession to improve and maintain**

❖ **Initial Upgraded Sections – Motorway Widening**

Junctions 16 to 23 and Junctions 27 to 30

1,900,000 m<sup>3</sup> of surplus cut to fill balanced

❖ **Later Upgraded Sections – Managed Motorway**

Junctions 5 to 7 and Junctions 23 to 27

300,000 m<sup>3</sup> of surplus cut to fill balanced

## Management of Earthworks Operations – M25 DBFO

- Site investigation and quality control of materials placed
- Specific soils managed and stockpiled for re-use
- Design and build to optimise material re-use
- Environmental Bunds Designed
  - Permanent visual screen provided
  - Noise levels reduced by up to half
  - Landform returned to agriculture
  - Sustainable solution
- Planning and landowner agreements
- Regular inspections by County Planning Landscape Officer

## Re-use in Earthworks Bunding – M25 DBFO



“I have especially enjoyed my relationship with SBB and am very proud of what we have achieved in such a short time”  
Hertfordshire County Council Restoration Manager Spatial and Land Use Planning

## Aggregates Recycling – M25 DBFO

### ➤ Initial Upgraded Sections – Motorway Widening

Junctions 16 to 23 and Junctions 27 to 30

Net importer of Construction & Demolition Waste

Over 1m tonnes processed into recycled aggregates on site

### ➤ Later Upgraded Sections – Managed Motorway

Junctions 5 to 7 and Junctions 23 to 27

Environmental Permit for crushing and screening on site

Over 100,000 tonnes processed and re-used on site



# Aggregates Recycling – M25 DBFO

## Recycling Achievements

- 92% of all aggregates used from recycled / secondary sources
- 2.4m tonnes used in total
- Net importer of C&DW
- Recovery into quality controlled aggregate products
- Departures from Standards - New specifications agreed

## Recycling Benefits

- Secure local supply
- On site supply minimised disruption to road network
- Reduction in over 10 million lorry miles
- 35,000t CO2e saved
- Financial benefits shared with client

## Use of Recycled Aggregates – M25 DBFO



Road Foundation layers



Widened Earthworks slopes




## Re-use of Contaminated Materials – M25 DBFO

- **M25 passed in cutting through 6 former landfill sites**
- Contamination leached into surrounding soils
- Detailed Ground Investigation and risk based analysis
- Specific zones to accommodate materials
- Acceptance criteria developed for each zone
- Colour coding and tracking system – Tickets and lorry windscreen cards
- Simple system of workforce engagement
- Volume of disposal reduced significantly

# Re-use of Contaminated Materials – M25 DBFO

Key:

**Disposal - Biodegradable**  
**Re-usable Materials**



Colour code classification zones:

U1B1 = **Red**

U1B2 = **Orange**

U1B3a = **Yellow**

U1B3b = **Blue**

U1B3c = **Green**

U1B4 = **White**



Colour coding classification included on permit to dig  
Each deposition zone marked with colour classification

# Contaminated Materials – M25 DBFO

Winner in category “Best Re-use of Materials” – Brownfield Briefing Awards 2011



Separation and excavation of landfill material



Indicator layer installed prior to backfilling with clean material for installing services

## **Re-use of Tar Bound Materials – A3 Hindhead**

- ❖ **4,500m<sup>3</sup> tar bound materials identified in existing A3**
- ❖ **Planings used as aggregate in bound road foundation layer**
- ❖ **Planings screened to required size – 20mm down**
- ❖ **Planings mixed with cement / PFA and bitumen through plant**
- ❖ **Foamix bound material laid with paver and compacted with vibratory rollers**
- ❖ **Saving in disposal off site – Hazardous Waste**
- ❖ **Saving in primary aggregates required**



## Processing of Tar Bound Road Planings – A3 Hindhead



Screening of planings to size



Mixing of foamix bound material



## Laying of Treated Tar Bound Road Planings – A3 Hindhead



Laying of foamix base



Compaction of foamix base

## **Re-use of Tar Bound Materials – A46 Newark**

- ❖ **Over 30,000 tonnes identified in existing A46 alignment**
- ❖ **Extensive pavement survey – all cores where tar identified from PAK-Marker spray tested for quantitative analysis**
- ❖ **Detailed risk based assessment to enable re-use**
- ❖ **Routine verification testing carried out to verify separation of tar bound and clean planings**

## Rapid Analysis of Tar Bound Materials – A46 Newark



Portable UVF testing apparatus




PAH levels determined to enable site control

## Re-use of Tar Bound Materials – A46 Newark

- ❖ Tar bound planings used as aggregate in bound road foundation layer
- ❖ Planings spread in layer to form 60/40 blend with primary aggregate
- ❖ Aggregate mixed with cement in-situ and compacted with vibratory rollers
- ❖ Saving in disposal off site – Hazardous Waste
- ❖ Saving in primary aggregates required



## Re-use of Tar Bound Materials – A46 Newark



Planings spread in layer to form 60/40 blend with primary aggregate



In-situ treatment of composite aggregate (planings and granite) to form bound road foundation



# Direct Transfer Between Projects – Heathrow T2b



## **Direct Transfer Between Projects – Heathrow T2b**

- ❖ **New Terminal 2b pier building to service A380 aircraft**
- ❖ **Suitable London Clay supplied to local project**
- ❖ **400,000m<sup>3</sup> re-used to create engineered cap to leaking landfill site**
- ❖ **Planning permission obtained by landfill operator**
- ❖ **400 loads per day exported from site**
- ❖ **Quality control of engineered clay cap**



# Direct Transfer Between Projects – Heathrow T2b



# Direct Transfer Between Projects – Bridgwater

Little Sydenham Farm Bridge Link Road





## Direct Transfer Between Projects – Bridgwater

- ❖ New link road to distribution centre
- ❖ 30,000m<sup>3</sup> of suitable fill materials imported
- ❖ Sourced from local projects (mainly housing developments)
- ❖ Inspected and tested at source to confirm suitability
- ❖ MMP updated regularly
- ❖ Quality control on site





# THANK YOU



**CONSTRUCTION SERVICES UK**

Thoughtful contributors to the built environment

**Balfour Beatty**